

Quotations Required for improvements to Harrowbarrow Car Park

Calstock Parish Council require quotes for remedial works to Harrowbarrow car park.

Location: Harrowbarrow Village Hall, School Road, PL17 8BQ 20-03-2023.



i) Area 1 Entrance to Car Park

Cut out an area from the present tarmac which has already been made good at the entrance to a line 4.5m into the car park and to the entrance kerbs/stone wall on the sides. The tarmac tapers in from the existing made good area to the entrance stone pillars and then opens out again. The widths at the entrance are:

- a) At the join to the existing good tarmac at the entrance and the kerb/stone wall 10.8m
- b) Between the entrance sone pillars 6.7m
- c) At the 4.5 mark into the car park and the kerbs 9.5m

The area to be cut out to a depth of 90mm and then repaired by laying with 90mm of tarmac in 2 layers compacted with a roller. The layers to be 60mm of 14mm dense binder course and 30mm of 10mm wearing course.

ii) Area 2 Entrance to Village Hall Road.

From the kerb stones laid flat at the entrance to the village hall road cut out an area the width of the village hall road (3.01m wide) and back from flat laid kerb stones by 4m cut out to a depth of 90mm. Replace with 2 layers of tarmac as above and grade down to the existing rain water drainage gully for adequate drainage to the area.

These tarmac repairs will have removed the present yellow hatched road markings at the entrance road. The contractor is to re-mark this area as at present following the completion of the resurfacing works.

iii) General areas

The contractor is to supply an addition cost for making good pot holes at the time that the works are carried out. This cost is not to be part of the quotation fixed cost but an addition cost for any pot hole repairs added by the Parish Council at the time of the works.

The contractor should visit the site before submitting the quotation to check dimensions and see the extent of the works.

Please submit quotes by Friday 31 March 2023

The Parish Council is not committed or obligated to commissioning works.